



Request for Proposals: Pedestrian Footbridge Wooden Deck Replacement
New Boston Conservation Commission
7 Meetinghouse Hill Road
New Boston, NH
603-487-2500 X161

The pedestrian footbridge located off of Gregg Mill Road, just north of River Road / State Route 13 over the Middle Branch of the Piscataquog River, coordinates 43.001747, -71.661435, requires a bridge deck replacement. The deck is 6'-0" wide and 83'-6" long and is currently constructed with 2 ½" thick horizontal planks resting on longitudinal wooden beams 5 ½" deep and 3 ½" wide. The deck rests on a steel box beam and c-channel bridge frame.

The work will consist of removing and disposing of the existing wooden deck and replacing it with a deck of sufficient material and thickness to support the loading from horses and equestrians. Upon completion of the work the work must be inspected and accepted by the Conservation Commission's appointed representative before the final payment will be made. No warranty is requested as part of the work, but the type of material specified should be expected to provide durability of at least 20 years.

Proposals are due electronically (to l.bernard@newbostonnh.gov) or on paper to Laura Bernard at the New Boston Town Hall no later than October 2, 2015. Work is to be complete by November 30, 2015.

Proposals must include all of the following items:

- Lump sum cost for all work
- Anticipated start of work and completion dates
- Type of material proposed, layout/design sketch, and sizes
- Payment terms
- Three references

Questions may be directed to Laura Bernard (l.bernard@newbostonnh.gov).

Pictures of the existing bridge follow on the next page.

